

# Step-by-Step Installation of 20ft High Cube 5MWh BESS for EV Charging Stations

2026-03-10 13:25

## Contents

- [The Silent Problem Slowing Down Your EV Charging Rollout](#)
- [Why This Hurts More Than Just Your Budget](#)
- [A Practical Path Forward: The 20ft, 5MWh Power Cube](#)
- [A Real-World, Step-by-Step Installation Guide](#)
- [Case in Point: Powering Up in the Midwest](#)
- [Expert Insights: The "Why" Behind the "How"](#)
- [What's Your Next Move?](#)

## The Silent Problem Slowing Down Your EV Charging Rollout

Honestly, when we talk about scaling up EV charging infrastructure in the US and Europe, everyone's focused on the chargers themselves—the ultra-fast 350kW units, the sleek payment systems. But there's a massive, often overlooked bottleneck hiding in plain sight: the grid connection. I've been on sites from California to North Rhine-Westphalia where ambitious EV charging projects get delayed for months, sometimes years, waiting for a grid upgrade. The local utility simply can't deliver the needed power capacity fast enough, or the upgrade costs run into the millions. This isn't a hypothetical; it's the daily reality for developers and site hosts.

## Why This Hurts More Than Just Your Budget

Let's agitate that pain point a bit. It's not just about delays. A weak grid connection means your expensive high-power chargers can't all operate at peak simultaneously without triggering penalties or causing brownouts. You're leaving revenue on the table. Worse, according to a [National Renewable Energy Laboratory \(NREL\)](#) analysis, demand charges from these sudden, high-power draws can constitute up to 90% of a commercial site's electricity bill. You're essentially paying a premium for the privilege of stressing the local grid. From a safety and compliance angle, pushing the limits of an existing service without proper management raises red flags with local inspectors and insurance providers. It's a financial, operational, and regulatory headache all rolled into one.

## A Practical Path Forward: The 20ft, 5MWh Power Cube

So, what's the solution I've seen work firsthand? It's not magic, but smart, pre-engineered infrastructure. The answer increasingly lies in deploying a Utility-scale Battery Energy Storage System (BESS) right at the charging site. And the workhorse that's proving incredibly effective is the standardized 20-foot High Cube containerized BESS, pre-configured with around 5MWh of capacity. This isn't a futuristic concept; it's a practical, plug-and-play(ish) solution that acts as a massive power buffer. It charges slowly and steadily from the existing, limited grid connection, then releases that energy in rapid bursts to multiple EVs simultaneously. At Highjoule, we've focused our utility-scale product line on making these units as site-ready, safe, and compliant as possible from day one, because on-site surprises are the last thing you need.





## A Real-World, Step-by-Step Installation Guide

Let's get practical. How does one of these 5MWh units actually get from the factory to powering your chargers? Here's the step-by-step, based on dozens of deployments.

### Phase 1: Pre-Site Preparation (Weeks 1-4)

This is where the real work happens, long before the container arrives. It starts with a detailed site assessment. We're looking for a level, stable concrete pad with proper drainage, within 30-50 meters of both the main grid connection point (the utility transformer) and the future EV charging array. Civil engineers finalize the foundation plans, which must account for the significant weight a 5MWh unit can weigh over 50 tons. Simultaneously, the electrical design is finalized, ensuring all switchgear, protection devices, and cable runs comply with local codes (NEC in the US, IEC/IEEE influences globally). Permitting is kicked off, with drawings stamped by a Professional Engineer (PE) being non-negotiable. All this groundwork is crucial for a smooth "lift-and-place" operation later.

### Phase 2: Delivery & Placement (The Big Day)

The container arrives on a specialized flatbed truck. With a 100-ton crane (sized with a healthy safety margin), the operation is methodical. The crane lifts the container, the site crew guides it, and it's gently lowered onto the pre-positioned leveling pads or anchor bolts on the foundation. The precision here is key—we need perfect alignment for the pre-fabricated cable entries to line up. Once placed, the first action is to secure it to the foundation with seismic-rated anchors, a must for UL 9540 certification and local building codes.

### Phase 3: Electrical Interconnection (Weeks 2-3 Post-Placement)

Now, the electricians take over. The medium-voltage or heavy-duty low-voltage cables are run from the utility point of interconnection (POI) to the BESS's main breaker. Another set of DC cables is run from the BESS to the EV charging station's power distribution cabinet. Every connection is torqued to spec, and every conduit is sealed. The heart of this phase is the commissioning of the Power Conversion System (PCS) and the Energy Management System (EMS). We

configure the EMS with the site's specific goals: peak shaving, demand charge reduction, or even providing grid services if the market allows.

## Phase 4: Testing & Grid Sync (The Final Check)

Before we even think about flipping the "on" switch, we run a full suite of functional tests. This includes insulation resistance tests, protection relay verification (making sure it will fault safely), and a full communication protocol check between the BESS, the chargers, and any upstream SCADA system. Finally, with utility approval, we perform a gradual grid synchronization. We start by importing a tiny amount of power, then export a bit, checking every meter and relay. Only after a 72-hour monitored soak test at various load levels do we sign off.

## Case in Point: Powering Up in the Midwest

Let me give you a real example. We worked with a logistics park in Ohio that wanted to install a fleet of 10 dual-port 150kW chargers for their electric trucks. The utility quoted an 18-month lead time and a \$1.2M cost for a grid upgrade. Instead, we deployed a single 20ft Highjoule 5MWh BESS on a prepared pad near their existing substation. The BESS charges overnight at a low, steady rate from their existing service. During the day, it powers the chargers while simultaneously shaving the site's overall peak demand. The result? The chargers were operational in 5 months. The avoided grid upgrade paid for the BESS, and they're now saving over \$15,000 monthly on demand charges. The site manager told me it was the only solution that made the business case work.

## Expert Insights: The "Why" Behind the "How"

As an engineer, I don't just care that it works; I care why it works sustainably. Let's break down three critical terms you'll hear.

- **C-rate:** This is simply the speed of charging or discharging. A 1C rate means the battery can be fully charged or discharged in 1 hour. For a 5MWh BESS, that's a 5MW power flow. For EV charging, we often use a lower, gentler C-rate for charging the BESS (like 0.25C or 1.25MW from the grid) and a higher one for discharging to the chargers (0.5C or 2.5MW). This mismatch is the whole point it lets you use a small grid pipe to fill a big bucket, then pour from that bucket quickly. Choosing the right C-rate chemistry (often LFP for this application) is crucial for longevity.
- **Thermal Management:** This is the unsung hero. Pushing megawatts in and out creates heat. A poorly managed system degrades fast. Our units use a liquid cooling system that directly contacts the battery cells, keeping the entire pack within a 2-3C temperature range. This isn't just about safety; it's about ensuring your 5MWh is still 5MWh in year 10, not 3.5MWh.
- **Levelized Cost of Storage (LCOS):** Think of this as the "true cost" of each kWh that comes out of your BESS over its lifetime. It includes the upfront capex, maintenance, degradation, and financing. A well-designed, thermally managed system with the right C-rate might have a higher upfront cost but a significantly lower LCOS because it lasts longer and performs better. This is the number your CFO actually cares about.

At Highjoule, designing for a low LCOS and full compliance with standards like UL 9540 and IEC 62619 isn't a marketing checkbox. It's what we build into the DNA of our containerized systems, because we're the ones who also get called for the 10-year service visit. We want that visit to be uneventful.





## What's Your Next Move?

Look, the transition to electric fleets and public charging isn't slowing down. The constraint is shifting from the charger technology to the grid's ability to support it. The 20ft, 5MWh BESS is proving to be the pragmatic, deployable answer right now. So, the question I'd leave you with is this: On your next EV charging project, will you be waiting in line for a grid upgrade, or will you be generating revenue with your own on-site power reservoir?

Author: John Tian

5+ years agricultural energy storage engineer / Highjoule CTO

URL: <https://gusroombrokers.co.za/articles/step-by-step-installation-of-20ft-high-cube-5mwh-utility-scale-bess-for-ev-charging-stations>

